

# Request for Quotations

	Tender	Description	Quantity	Sample/Specs
1.	782-20	Supply And Delivery Of 8 Port Switch With Accessories 2960 Series CISCO	50	Samples at Apparatus Store, Epton Street
2.	783-20	Supply And Delivery Of SFP CISCO 1000 Base -LX-LIT 10KM	15	Sample at Apparatus Store, Epton Street
3.	784-20	Supply And Delivery Of Fibre Patch Panel 24 Port 19" 1U	100	Samples Apparatus Store, Epton Street
4.	785-20	Supply And Delivery Of Wall Mount Termination Box	200	Samples Apparatus Store, Epton Street
5.	78620	Supply And Delivery Of CAT6 Molex Patch Cords (3m)	5000	Samples Apparatus Store, Epton Street
12.	787-20	Supply And Delivery Of Metered Rack Mounting Power Distributed Units	3	Specifications attached
13.	788-20	Repair Of Thrust Boring Hammerhead Catamount Mole	2	Viewing Of The Machines At Telone Projects, Epton Street Contact 0732 973 372 Nyadzisa Mukwaira
14.	789-20	Supply And Delivery Of Malico Drop Wire Clamps With Hooks	10000	Samples Apparatus Store, Epton Street
15.	790-20	Supply And Delivery Of CAT6 Molex Outdoor Cable	10000m	Samples Apparatus Store, Epton Street
16.	791-20	Supply And Delivery Of Stay Rods 46 X 5/8"	1000	Samples at OHL Msasa, Msasa
17.	792-20	Supply And Delivery Of Stay Rods 46 X 1/2"	1000	Samples at OHL Msasa, Msasa
19	793-20	Supply And Delivery Of 5/8 X 6ft Rod Earthing	100	Samples at OHL Msasa, Msasa
20	794-20	Supply And Delivery Of 15mm Sink Mixer	12	Samples at General store, Epton st
21	795-20	Supply And Delivery Of Matchets With Hook	300	Samples at Tool store, Epton st
22	796-20	Supply And Delivery Of Super Contact Adhesive Glue 1litre	60	
23	797-20	Supply And Delivery Of Drill Mason Master 8mm	60	Samples at Tool store, Epton st
24	798-20	Supply And Delivery Of Drill Mason Master 6mm	60	Samples at Tool store, Epton st
29	803-20	Supply And Delivery Of 9v Batteries Energiser	1000	Sample at Apparatus store, Epton st
30	804-20	For The Supply And Delivery Of Cartridges 1. PFI-703MBK-700ML Matte Black Ink Cartridges 2. PFI-703BK-700ML Black Ink Cartridges 3. PFI-703M-700ML Magenta Ink Cartridge 4. PFI-703Y 700ML Yellow Ink Cartridges 5. PF-03 Print Head 6. MC-09 Maintenance Cartridge	1 1 1 1 1 1	
31	805-20	For The Supply And Delivery Of 1. Laptop Bag 2. Wireless Mouse-Original Quality Brand	1 1	Specs attached, to be supplied as per specs attached please for executives
32	806-20	For The Supply And Delivery Of Samsung Galaxy S20 Dual Sim.	1	CELLPHONE MUST BE AVAILABLE IN STOCK
33	807-20	For The Supply, Installation And Commissioning Of Two By 24 000btu/H Midwall Split Air-Conditioning Units In KWEKWE. 1. Rutendo 2. Msasa	1 1	SPECS ATTACHED
34	808-20	Supply And Delivery Of All In Core I5 One Pcs PCS MUST BE AVAILABLE IN STOCK NO CHANCERS AS ORDERS WILL BE CANCELLED FOR LATE DELIVERIES	4	SPECS ATTACHED
35	809-20	Provision Of A Contractor For Ceiling Repairs At Victoria Falls		Specs Attached
36	810-20	Provision Of A Contractor For The Following Works At Zvishavane Exchange: • Repairs To Palisade Fence • Durawal Repairs • Construction Of A Guard House		Specs attached Compulsory Site Visit Date: 29 September 2020 Time: 1100Hrs
37	811-20	Provision Of A Contractor For Borehole Drilling At Zvishavane Exchange		Specs attached
38	812-20	Provision Of A Contractor For Hillside Paving Labour Only		Specs attached
39	813-20	Supply And Delivery Of Plumbing Materials		Specs attached
40	814-20	Supply And Delivery Of Hardware Materials		Specs attached
41	815-20	Supply And Delivery Of Tiling Materials		Specs attached
42	816-20	Provision Of A Contractor For The Construction Of Nkulumane Exchange Durawal		Specs attached
43	817-20	Supply And Delivery Of Heatshrinks 530-55-112-250-300	500	Samples at Cable Store, 22 George Drive, Msasa
44	818-20	Supply And Delivery Of Heatshrinks 530-100/25-460	500	Samples at Cable Store, 22 George Drive, Msasa
45	819-20	Supply And Delivery Of Heatshrinks 530-43/8-150	500	Samples at Cable Store, 22 George Drive,

				Msasa
46	820-20	Supply And Delivery Of Heatshrinks 530-75/15-240	500	Samples at Cable Store, 22 George Drive, Msasa
47	821-20	Supply And Delivery Of CISCO Switch 24 Port Gigabit Poe RUCKUS Indoor Access Points – R310	6 15	
48	826-20	Supply And Delivery Of Business Cards	1 set	250 per set
49	827-20	Supply And Delivery Of Umbrellas	50	Sample available for viewing

Please note that **only** bidders registered with **Procurement Regulatory Authority of Zimbabwe (PRAZ)** shall be considered.

(Please attach Proof of PRAZ registration in the specified category)

**Closing date for ALL Tenders: On or before 1100hrs; Wednesday 30<sup>th</sup> of September 2020**

Your Tender should state the price( Please state your **VAT** status), a firm delivery date and be placed in the tender box on the 8th Floor, South Wing, Runhare House , 107 Kwame Nkrumah Avenue, Harare; OR Emailed to [procurement@telone.co.zw](mailto:procurement@telone.co.zw)

Tel; 264 242 798111; Fax 264 242 795499 Runhare House, 107 Kwame Nkrumah Avenue, Harare,

#### RFQ 808-20

#### Core i5 All-in-One PC

Feature	Description	Compliance
<b>Operating system</b>	Windows 10 Pro 64	
<b>Processor</b>	Intel® Core™ i5 3 GHz base frequency	
<b>Display</b>	21.5" diagonal FHD IPS widescreen LCD anti-glare WLED-backlit (1920 x 1080)	
<b>Memory</b>	8 GB DDR4-2666 SDRAM (1 X 8 GB)	
<b>Memory slots</b>	2 SODIMM	
<b>Hard drive</b>	1 TB 7200 rpm SATA	
<b>Optical drive</b>	Slim DVD-Writer	
<b>Ports</b>	Front; 1 microphone/headphone jack, 2 USB 3.0, Back: 1 HDMI, 1 power connector, 1 RJ-45, 1 VGA, 2 US	
<b>What's in the Box</b>	CPU, Monitor, Keyboard, Mouse, power cords, user guide	
<b>Warranty</b>	12 months	
<b>Color</b>	Gray/Black	
<b>Webcam</b>	1 MP HD webcam with integrated digital microphone	
<b>Audio</b>	Universal audio jack, and 2W internal speaker	
<b>Form factor</b>	All-in-one Desktop PC	
<b>Pointing device</b>	USB Optical Mouse	
<b>Keyboard</b>	USB Business Slim Wired Keyboard	
<b>Power</b>	220V AC or DC12V 5A Power supply	
<b>Warranty</b>	1 year	

Inquiry No 787-20

**PDU SPECIFICATIONS**

**1. Output Connections:**

(36) IEC 320 C13  
 (36) IEC 60320 C13  
 (6) IEC 60320 C19  
 (6) IEC 320 C19  
 Nominal Output Voltage: 230V  
 Nominal Input Voltage: 200V, 208V, 230V  
 Input Connections: IEC 60309 32 A 2P + E  
 Nominal Input Voltage: 200V, 208V, 230V  
 Input frequency: 50/60 Hz  
 Input Connections: IEC 60309 32 A 2P + E  
 Acceptable Input Voltage: 220 - 240VAC  
 Load Capacity: 7400VA  
 Maximum Input Current: 32A  
 Maximum Line Current: 32A  
 Part number: AP8853

**2. Physical Dimensions**

Maximum Height 1791mm  
 Maximum Width 56mm  
 Maximum Depth 44mm  
 Color Black

**3. Environmental**

Operating Temperature -5 - 45 °C  
 Operating Relative Humidity 45- 55 %  
 Operating Elevation 0 - 3048 meters  
 Storage Temperature - 25 - 65 °C

**4. The PDU should also provide the following:**

- Local Current Monitoring Display
- Load indicator LED
- Rack mountable and occupying Zero U of rack space
- Web based remote monitoring capabilities
- User-defined alarm thresholds to mitigate risk with real-time local and remote alerts to warn of potential circuit overloads
- Active metering to enable energy optimization and circuit protection.
- A temperature/humidity sensor port, locking IEC receptacles, and ultra-low profile circuit breakers.
- Have in-built power banks
- Conforms to IEC 60950 and is RoHS Compliant

**Inquiry No. 807-20**

**The Scope of Works Include:**

- Supply, installation and commissioning of the four air conditioning units.
- The air conditioning units shall be cooling only and shall be controlled via a wireless remote controller.
- The unit shall be a DC inverter
- The refrigerant must be R410A or any other environmentally friendly refrigerant with an ODP of zero.
- TelOne prefers the DB or LG brands only.
- TelOne expects a product warranty of 12 months.
- The contractor is expected to perform quarterly services during the warranty period and the quoted price should be **inclusive** of these services.
- Contractor shall also provide the circuit breakers, cabling and other accessories required to provide power for the units.
- Estimated run not expected to exceed 6m per unit.

**Inquiry No.816-20**

Telone  
 Nkulumane Exchange Durawall Repairs  
 Bulawayo

Item	Description	Unit	Quantity	Rate	Amount
<b>Durawall Repairs</b>					
A	Remove the existing durawall precast concrete panels and columns. Stack the concrete panels on site as instructed by the Client and remove the rubble offsite. Carefully remove the razorwire for reuse.	m	220.00		-
B	Install plain precast concrete panels measuring 1600mm x 180mm high, installed in between precast concrete columns 2100mm high above the natural ground level, spaced at 1600mm c/c including concrete bases at the bottom of the concrete columns. The precast panels to be installed in cement-sand mortar between the panels and the concrete columns. The panels should match the existing.	m	220.00		-
C	Reinstall the barbed wire and make good	m	220.00		-
D	Leave the site clean and remove any excess materials, rubble and / or debris.	Item	1.00		-
E	Preliminaries and Generals	Item	1.00		-

**Inquiry 814-20**

Item	Description		Qty	Unit Price	Total Price
1	Cement	50kg bags	65		
2	Stone	m3	10		
3	Bonding Liquid	Litres	60		
4	2,240 x 1,220 Bison Boards	Sheets	14		
5	Panel Pins	kg	2		
6	Ceiling White	litres	10		

### Inquiry 813-20

Lots 1-4

Item	Description		Qty	Unit Price	Total Price	
1	5000litres Jojo Tank	No.	1			lot 1
2	Close Coupling	No.	1			lot 2
3	Bath Tub Acrylic	No.	1			
4	Bath Tub Waste fitting	No.	1			
5	Bath Tub Mixer (Pillar Tape)	No.	1			
6	15mm Flexi Connector Braided.	No.	1			
7	20mm brass ball cock	No.	1			
8	40mm PVC plain bend	No.	2			
9	40mm PVC ball cock valve	No.	1			
10	40mm PVC pipe	6m Length	1			
11	15mm MLP Pipes	m	20			
12	20mm gate valve	No.	5			
13	20mm copper tee	No.	1			
14	20mm copper elbows	No.	2			
15	15mm gate valve	No.	2			
16	15mm copper tee	No.	2			
17	Toilet Roll Holders	No.	1			
18	1 HP Booster Pump		1			
19	Pump Auto Control		1			
20	40mm PVC pipe class 16		12m			lot 4
21	40mm PVC Cock Valve		1			
22	40mm PVC socket Union		1			
23	40 x 32mm PVC reducing bushy		1			
24	40mm PVC bend plain		2			
25	40mm x 1.5" VSP male		1			
26	32mm PVC pipe class 16		6m			
27	32mm PVC socket Union		2			
28	32mm PVC bend plain		6			
29	32mm x 25mm VSP male		2			
30	200ml Solvent Cement		1			

### Inquiry No.812-20

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<b>HILLSIDE EXCHANGE REFURBISHMENT</b>					
<b>EXTERNAL WORKS</b>					
<b>BILL NO. 1</b>					
<b>PARKING AND PAVING</b>					
<b>Tree Removal</b>					
A	Remove trees having a trunk circumference not exceeding 1000mm measured 1 metre above ground, grubbing up and removing all roots and filling in with suitable materials and well consolidating	No.	4		
B	Remove trees having a trunk circumference exceeding 1000mm not exceeding 2000mm measured 1 metre above ground, grubbing up and removing all roots and filling in with suitable materials and well consolidating	No.	3		
<b>Site clearance</b>					
C	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc and trees not exceeding 200mm girth	m2	1200		
D	Compaction of ground surfaces under pavings etc, including rip, scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m2	1200		
<b>Disposal, formation etc.</b>					
Earth filling supplied by the contractor from his own sources under parking areas, roadways, etc					
<b>Hardcore provided by the Contractor.</b>					
E	Selected and approved clean hard dry hardcore material compacted to in layers not exceeding 150mm thick to 95% HCE to falls and cross-falls	m3	10		
					Amount Carried Forward
					\$
HILLSIDE EXCHANGE REFURBISHMENT - PAVING Bill No. 1 EXTERNAL WORKS					

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					Amount Brought Forward
					\$
60mm Thick 35MPa precast concrete interlocking paving of 100 x 220mm chamfered grey (untinted) paving blocks, laid to falls on and including 20mm thick sand layer with joints filled in with sand, compacted with a vibration compactor.					
<i>Pavers Supplied by the Client.</i>					
A	Paving to parking areas to falls.	m2	1100		
B	Allow for preliminaries and generals				

### Inquiry 810-20A

Item	Description	Unit	Quantity	Rate	Amount
<b>BRICKWORK</b>					
A	Install 500 x 500mm copings	No.	15.00		-
<b>PLASTERING</b>					
One coat 1:4 cement plaster finished to wood float.					
B	On walls	m2	138.00		-
<b>WROT IRON SCREENS</b>					
Carefully remove the existing screen infills and refabricate the screens using the recovered materials including any additional steel member to match the existing. Including reinstalling the screens to the existing brick works to the approval of the Client.					
C	Screen Size 1700 x 2400	No.	1.00		-
D	Screen Size 2500 x 2400	No.	3.00		-
E	Screen Size 2600 x 2400	No.	2.00		-
F	Screen Size 2800 x 2400	No.	1.00		-
G	Screen Size 3000 x 2400	No.	5.00		-
<b>PAINTING</b>					
<b>ON PLASTER</b>					
Prepare, stop and apply two coats interior quality acrylic PVA emulsion paint					
H	On internal steel float finish plaster	m2	138.00		-
<b>ON METAL</b>					
Prepare and apply two finishing coats high gloss enamel paint.					
I	On screens	m2	79.00		-
J	Allow for touch-ups including leave the site clean of any debris	Item	1.00		-
K	Allow for Preliminaries and Generals	Item	1.00		-

**Inquiry No.810-20B**

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u> <u>GUARD HOUSE</u> <u>BILL NO. 1</u> <u>BRICKWORK</u> <u>Approved blocks in 1:4 cement mortar built fair both sides (plastering elsewhere measured)</u>						<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u> <u>GUARD HOUSE</u> <u>BILL NO. 2</u> <u>ROOF COVERINGS</u> Note: All holes through roofing sheets are to be drilled and not punched <u>Roof Installation</u>					
A	115 mm brick walls	m2	5	-		A	Install new IBR roof sheets.	m <sup>2</sup>	5	-	
B	Approved brick reinforcement for 115 mm brick wall, lapped at angles and passings (measured net) (every second courses)	m	10	-			<u>Sawn softwood</u>				
C	Rough raking cutting and waste	m2	3	-		B	50 X 76 Purlins	m	7	-	
D	Bed wall plates in 1:5 cement mortar	m2	3	-							
<u>Sundries</u>											
ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u> <u>GUARD HOUSE</u> <u>BILL NO. 3</u> <u>JOINERY AND IRONMONGERY</u> <u>DOORS</u> <u>44 mm Exterior quality hardwood door suitable for painting</u>						<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u> <u>GUARD HOUSE</u> <u>BILL NO. 4</u> <u>PLASTERING AND WALL LININGS</u> <u>PLASTERING</u> <u>One coat 1:4 cement plaster finished smooth with a steel trowel internally</u>					
A	Door size 813 x 2032 mm high	No	1	-		A	On walls	m2	16	-	
B	Three lever mortice lockset	No	1	-		B	On walls in narrow widths	m2	1	-	
<u>IRONMONGERY</u> <u>Union or similar and approved locks, etc</u>						<u>One coat 1:4 cement plaster finished to wood float</u>					
						C	On walls	m2	16	-	
						D	On walls in narrow widths	m2	1	-	
ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT						
<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u> <u>GUARD HOUSE</u> <u>BILL NO. 5</u> <u>PAVINGS AND FLOOR COVERINGS</u> <u>Untinted granolithic pavings</u>											
A	40 mm pavings steel trowelled smooth on concrete floors	m2	4	-							

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>ZVISHAVANE EXCHANGE REFURBISHMENT</u>						<u>ZVISHAVANE EXCHANGE REFURBISHMENT - GUARD HOUSE</u>					
<u>GUARD HOUSE</u>						<u>SUMMARY</u>					
<u>BILL NO. 6</u>						Bill No					
<u>PAINTING</u>						Page No					
<u>ON PLASTER</u>						1	BRICKWORK		1		-
<u>Prepare, stop and apply two coats interior quality acrylic PVA emulsion paint</u>						2	ROOF COVERINGS		2		-
A	On internal steel float finish plaster	m2	16		-	3	JOINERY AND IRONMONGERY		3		-
B	On external wood float finish plaster	m2	16		-	4	PLASTERING AND WALL LININGS		4		-
<u>ON WOOD</u>						5	PAVINGS AND FLOOR COVERINGS		5		-
<u>Prepare and apply one coat pink wood primer, one undercoat and two finishing coats high gloss enamel paint</u>						6	PAINTING		6		-
C	On general surfaces of doors (both sides measured)	m2	4		-	SUB-TOTAL					-
	On door frames	m2	1		-						-
<u>TOUCH UP</u>											
D	Touch up and clean paintwork requiring it, scrub floor and clean down glass and clean paintwork requiring it, scrub floor and clean down glass and leave premises and site properly clean and the whole complete and ready for occupation	Item	1		-						

### Inquiry No.809-20

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>CEILING REPAIRS AT NUMBER 526 REINARD, VICTORIA FALLS</u>						D	Extra over trimming ceiling to form access opening size 750 x 750 mm in clear, including trap, formed of 5 mm primed hardboard on 38 x 76 mm wrot trimmers framed around opening and 19 x 76 mm wrot angle-rounded softwood planted on and mitred around at junction with ceiling	No	1		-
<u>ROOF REPAIRS</u>						E	75 mm Standard coved cornice	m	120		-
A	Attend to roof isolated roof leaks, by using super laycral or an approved roof sealant.	Item	1		-	<u>PAINTING</u>					
<u>CEILINGS</u>						<u>Prepare and and apply one undercoat and two coats PVA on bison boards</u>					
B	Remove the existing bison and rhino boards and handover to the Client.	m2	180		-	F	To ceilings	m2	180		-
<u>6 mm bison board ceiling set out symetrical in panels with equal margins with 6 mm wide open joints and fixed in strict accordance with the manufacture's instructions</u>						G	Touch up and clean paintwork requiring it, scrub floor and leave premises and site properly clean and the whole complete and ready occupation.	Item	1		-
C	Bison board ceiling fitted to and including 38 x 38 mm sawn softwood brandering at 400 mm centres one way notched into, nailed and including 50 x 75 mm brandering at right angles to 38 x 38 mm brandering spaced 400 mm centres one way and 38 x 50 mm brandering all round next to walls, skew nailed to ceiling joists (elsewhere measured) and cover joints with and including 16 x 32 mm pre-primed wrot soft wood cover strips planted on	m2	180		-	H	Allow for preliminaries and generals	Item	1		-
						SUB-TOTAL					
						Add: VAT					
						TOTAL AMOUNT					

**Inquiry No 810-20C**

**Background**

A portion of the durawall at Zvishavane Exchange was damaged by a vehicle and exposing the Exchange to a security risk as members of the public can easily access the site. Another portion was not completed by the contractor who constructed the palisade fence hence it needs to be concluded.

The scope of works shall entail the following;

- Removing the existing 6m Durawall Panels,
- Installation of 17m Durawall panels,
- Making good the site.

**Inquiry No.805-20**

**Padded Laptop Bag Specifications**

The carry case must be designed with a **padded divider** that can be positioned to meet varied needs. The case must have separate side storage areas for accessories, eg remote control/cell phone.

- Adjustable internal divider
- Capable to fit 15 inch laptop
- Exterior of black ballistic nylon which is abrasion and moisture resistant
- Padded no-slip shoulder strap
- Accessory pockets to fit cords, cables and/or remote control
- Case to meet Airline Carry-on Restrictions

**Inquiry No 811-20**

**Zvishavane Exchange Borehole Drilling**

Ref	Description	Unit Price	Total Price
a	Siting of borehole and submission of report		
b	Zinwa Permit application and Zvishavane Town Council		
c	40m borehole drill and casing (full) and submission of drilling report		
d	Capacity test and submission of report		
e	Supply and fit submersible pump installation 1HP complete with control box and connection to to electrical supply(allow cabling)		
f	Supply and fit steel pressure tank and pressure switch and connect to borehole and electrical supply		
g	Supply and fit 3.6m (height above ground) steel tank stand completed with service ladder, meshed platform and painted with gloss enamel finish		
h	Supply and fit 5000l tank complete with ball valve		

	Supply and connect of borehole to building including isolator valves and non-return valve. (allow 70m pipework -exposed pipes to be of galvanized or PVC class 16) connection of borehole to building including isolator valves and non-return valve. ( allow 70m pipe work)		
i			
j	Supply and fit lockable security manhole cover for borehole pump		
	<b>Additional Costs per metre</b>		
k	Drilling		
l	Casing		
j	1.5mm <sup>2</sup> SWA armoured cable		
	Milage		
	<b>Sub-Total</b>		-
	VAT	0.15	-
	<b>GRAND TOTAL</b>		-



**Inquiry No 816-20**

Telone  
Nkulumane Exchange Durawall Repairs  
Bulawayo

Item	Description	Unit	Quantity	Rate	Amount
<b>Durawall Repairs</b>					
A	Remove the existing durawall precast concrete panels and columns. Stack the concrete panels on site as instructed by the Client and remove the rubble offsite. Carefully remove the razorwire for reuse.	m	220.00		-
B	Install plain precast concrete panels measuring 1600mm x 180mm high, installed in between precast concrete columns 2100mm high above the natural ground level, spaced at 1600mm c/c including concrete bases at the bottom of the concrete columns. The precast panels to be installed in cement-sand mortar between the panels and the concrete columns. The panels should match the existing.	m	220.00		-
C	Reinstall the barbed wire and make good	m	220.00		-
D	Leave the site clean and remove any excess materials, rubble and / or debris.	Item	1.00		-
E	Preliminaries and Generals	Item	1.00		-

**Inquiry No.812-20**

Telone  
Nkulumane Exchange Durawall Repairs  
Bulawayo

Item	Description	Unit	Quantity	Rate	Amount
<b>Durawall Repairs</b>					
A	Remove the existing durawall precast concrete panels and columns. Stack the concrete panels on site as instructed by the Client and remove the rubble offsite. Carefully remove the razorwire for reuse.	m	220.00		-
B	Install plain precast concrete panels measuring 1600mm x 180mm high, installed in between precast concrete columns 2100mm high above the natural ground level, spaced at 1600mm c/c including concrete bases at the bottom of the concrete columns. The precast panels to be installed in cement-sand mortar between the panels and the concrete columns. The panels should match the existing.	m	220.00		-
C	Reinstall the barbed wire and make good	m	220.00		-
D	Leave the site clean and remove any excess materials, rubble and / or debris.	Item	1.00		-
E	Preliminaries and Generals	Item	1.00		-

<b>Compaction of surfaces</b>					
D	Compaction of ground surfaces under pavings etc, including rip, scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m2	1200		
<b>Disposal, formation etc.</b>					
Earth filling supplied by the contractor from his own sources under parking areas, roadways, etc					
<i>Hardcore provided by the Contractor.</i>					
E	Selected and approved clean hard dry hardcore material compacted to in layers not exceeding 150mm thick to 95% HCE to falls and cross-falls	m3	10		
<b>Amount Carried Forward</b>					\$
HILLSIDE EXCHANGE REFURBISHMENT - PAVING					
Bill No. 1					
EXTERNAL WORKS					

## Inquiry No. 812-20

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	
	<u>HILLSIDE EXCHANGE REFURBISHMENT</u>					
	<u>EXTERNAL WORKS</u>					
	<u>BILL NO. 1</u>					
	<u>PARKING AND PAVING</u>					
	Tree Removal					
A	Remove trees having a trunk circumference not exceeding 1000mm measured 1 metre above ground, grubbing up and removing all roots and filling in with suitable materials and well consolidating	No.	4			
B	Remove trees having a trunk circumference exceeding 1000mm not exceeding 2000mm measured 1 metre above ground, grubbing up and removing all roots and filling in with suitable materials and well consolidating	No.	3			
	Site clearance					
C	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc and trees not exceeding 200mm girth	m2	1200			
						Amount Carried Forward
						\$
						HILLSIDE EXCHANGE REFURBISHMENT - PAVING Bill No. 1 EXTERNAL WORKS

## InquiryNo.807-20

### The Scope of Works Include:

- Supply, installation and commissioning of the four air conditioning units.
- The air conditioning units shall be cooling only and shall be controlled via a wireless remote controller.
- The unit shall be a DC inverter
- The refrigerant must be R410A or any other environmentally friendly refrigerant with an ODP of zero.
- TelOne prefers the DB or LG brands only.
- TelOne expects a product warranty of 12 months.
- The contractor is expected to perform quarterly services during the warranty period and the quoted price should be **inclusive** of these services.
- Contractor shall also provide the circuit breakers, cabling and other accessories required to provide power for the units.
- Estimated run not expected to exceed 6m per unit.

## Inquiry No. 815-20

### RFQ815-20 Supply and delivery of tiling materials

Item Ref.	Description	Qty	Unit
A	Floor tiles ceramic 500mm x 500mm or 600mm x600mm	165sqm	sqm
B	Toilet tiles [wall]	26sqm	sqm
C	Paint 2 X20 LITRES [ EGG SHELL ] IVORY	40L	LITRES
D	Ceiling boards Bison boards 2440mm x 1220mm x 6,4mm	4 sheets	sheets
E	Steel handles	11	each
F	Super glue	1	5L
G	1 x sheet Formica 2440 by 1220	1	sheet
H	cement	6	bags
I	Block board 2440 by 1220	2	boards
J	tylon	90	20kg
K	grout	30	5kg
M	2 pairs cupboard hinges	2	pairs
N	Bonding liquid	12	5L