

REQUEST FOR QUOTATIONS

SLOT 3 CLOSING 13 NOVEMBER

2024

SHURUGWI RENOVATIONS/REPAIRS 10 DOUGLAS SMITH

CONTACT PERSON MR CHIMHUYA 0712097551

ITEM	RFQ No	DESCRIPTION	UNIT	QUANTITY
1	1479-24	DEMOLITIONS		
		Remove plastering right round the structure	m ²	498
		Remove all Pressed steel window frames:		
		ND11F 2000 X 1245mm	no.	3
		NE4F 1511 x 654mm	no.	2
		ND4F 1511 x 1245mm	no.	1
		NC5F 533 X 949mm	no.	2
		NC4F 1511 x 949mm	no.	1
		NC22F 2000 x 949	no.	1
		Remove all Pressed Steel Door Frames:		
		Standard 115mm Door frame	no.	5
		Fanlight Door frame suitable for 115 mm wall	no.	4
		230mm Door frame suitable for stable door	no.	1
		Standard 230mm Door frame	no.	1
		Remove timber window frame size 3850 x 1600mm	no.	1
		Demolish stone work	m ²	11
		Demolish brickwork 1.5m from wall plate: 230mm	m ²	270
		115mm	m ²	171
		Cart away all rubbles to an approved municipal dump site	sum	1
		sub-total		

--	--	--	--	--

2	Concrete Work		
	Concrete(30 Mpa)		
	Ring Beam	m ³	2
	Lintols - cast insitu	m ³	1
	Shuttering	m ²	40
	Reinforcement (all sizes)	kg	450
	sub-total		
3	Brick up to roof level		
	Half brickwork in common bricks in cement mortar	m ²	58
	One brickwork in common bricks in cement mortar	m ²	92
	E.O for pointing and jointing of the inner face (face brick)	m ²	11
	One brickwork in face bricks in cement mortar, pointed and Jointed	m ²	11
	Beam filling	m ²	4
	Stone work cladding	m ²	11

	Set in position and build in window and door frames n.e 5 m ²	no.	21
	Set in position and build in window frame n.e 10 m ²	no.	1
	Brickforce in half brick walls	m	171
	Brickforce in one brick walls	m	270
	Dpc under cills 230mm walls	m ²	11
	Bullnose cills	m	20
	Air vents	no.	27
	Hoop Iron Ties	no.	60
	sub-total		
4	<u>Roof Coverings</u>		
	0,58mm Chromadek with overall width of 740mm, 4 pans, with cover width of 686mm and 2100mm long	sheets	116
	Ridge capping (2.4m long)	no.	7
	sub-total		
5	<u>Roof Construction</u>		
	Roof Structural timber		
	114 x 38mm x 6m	length	150
	152 x 38mm x 6m	length	30
	76 x 38mm x 6m	length	53
	238 x 38 x 3m	length	5
	Branding 38 x 38mm x 6m	length	650
	Asbestos Fascia and badge boards 3.6m	length	20
	4 inch nails	kgs	18
	5 inch nails	kgs	15
	3 inch nails	kgs	15
	Clout nails	kgs	5
	Bolts (M10 x 120)	no.	200
	Valley gutters	no.	3
	Truss hangers	no.	50

	sub-total		
6	<u>Carpentry and Joinery</u>		
	Rhino board Ceiling boards	m ²	130
	Rhino Cornice	m	220
	Interior quality Flush door size 44 x 813 x 2032mm	no.	9
	Exterior quality solid door size 44 x 813 x 2032mm	no.	1
	Exterior quality stable door size 44 x 813 x 2032mm	no.	1

	3 Lever mortice lockset	no.	11
	sub-total		
7	<u>Metal work</u>		
	Pressed steel Window frames		
	ND11F 2000 X 1245mm	no.	3
	NE4F 1511 x 654mm	no.	2
	ND4F 1511 x 1245mm	no.	1
	NC5F 533 X 949mm	no.	2
	NC4F 1511 x 949mm	no.	1
	NC22F 2000 x 949	no.	1
	<u>Pressed Steel Door Frames</u>		
	Standard 115mm Door frame	no.	5
	F-anlight Door frame suitable for 115 mm wall	no.	4
	230mm Door frame suitable for stable door	no.	1
	Standard 230mm Door frame	no.	1
	Supply and fix fire place Jet master	no.	1
8	<u>Glazing</u>		
	3mm clear glazing	m ²	14
	3mm obscured glazing	m ²	2
	6mm clear glass	m ²	6
9	<u>Plastering and Wall Linings</u>		
	One coat of cement and sand (1:5) plaster finished smooth with a steel float Incl reveals	m ²	308
	One coat of cement and sand (1:5) plaster finished smooth with a wood float Incl reveals for external walls	m ²	170
	Damp the surface, supply and fix 150 x 150mm ceramic wall tiles applied in tylon adhesive, grouted, jointed and cleaned up	m ²	40
	<u>Skimming of walls</u>	m ²	130
	sub-total		
10	<u>Pavings and Floor Finishings</u>		
	Damp the surface and apply 40mm screed	m ²	135

	Damp the surface, supply and fix 400 x 400mm ceramic floor tiles applied in tylon adhesive, grouted,jointed and cleanedup	m ²	135
	Skirting 75 x 400mm (ceramic floor tiles)	m	135
	sub-total		
11	Painting		

	Apply 3 coats PVA paint internally on walls incl reveals	m ²	130
	Apply 3 coats PVA paint external Quality on walls incl reveals	m ²	179
	Apply 3 coats ceiling white	m ²	132
	Apply under coat and 2 coats gloss enamel paint on steel Frames	m ²	64
	Ditto on timber doors	m ²	39
	Brick dressing (Face brick)	m ²	53
	sub-total		
12	<u>Specialist works</u>		
	<u>SANITARY FITTINGS</u>		
	Supply and fixing of a closed couple (WC) complete with cistern and all fittings	no.	1
	Supply and fixing of a bath tub	no.	1
	Supply and fixing of a bath tub mixercomplete with fittings	no.	1
	Supply and fixing of a wash hand basin complete with pedestal, pillar taps and fittings	no.	1
	Supply and fixing of a stainless sink doublebowl coplete with bib taps, p- traps and fittings	no.	1
	Supply and fixing of a tissue roller holder	no.	1
	Supply and fixing of a hat and coat hook	no.	2
	Supply and fixing of a 150l solar geyser	no.	1
	Supply and fixing of 32mm copper pipe	lengt h	1
	Supply and fixing of 22mm copper pipe	lengt h	1
	Supply and fixing of 22mm copper elbows	no.	4
	Supply and fixing of 22mm copper reducers	no.	4
	<u>RAIN WATER GOODS</u>		
	Supply and fixing of seamless gutters 110mm	m	35
	Supply and fixing of seamless down pipes100mm x 75mm 1600mm full length	no.	4
	E.O for gutter offset	no.	4
	E.O for downpipe shoe	no.	4
	Supply and fixing of gutter brackets	no.	34

	Supply and fixing of downpipe holder bats	no.	12
	SKIRTING		
	Concrete skirting around the house Grade 25 MPA	m ³	3
	ELECTRICAL INSTALLATION		
	Chasing combs	no.	4
	19mm conduit pipes	length	30
	3 x 3 flash box	no.	8
	6 x 3 flash box	no.	10

8 way DB	no.	1
Meter Box	no.	1
Earth spike and rod	no.	1
D-Iron and shackle with spindle	no.	1
Nipples 19mm	no.	100
19mm couplings	no.	100
19mm saddles	no.	100
25mm conduit	length	2
25mm coupling and nipple	no.	5
Lugs 2.5mm	no.	20
Verandah bolts	no.	30
1.5mm red	roll	1
1.5mm black	roll	1
1.5mm earth	roll	1
2.5mm red	m	80
2.5mm black	m	80
2.5mm earth	m	80
4mm red	m	15
4mm black	m	15
4mm earth	m	15
Insulation tape red	no.	1
Insulation tape black	no.	1
Insulation tape yellow/ green	no.	1
Sprague tube and dome cover	m	1
Round junction and covers	no.	45
Bond strip	m	2
Self-taping screws	box	1
Clout nails	kgs	1
Concrete nails	kgs	1
MCB 60A	no.	1
MCB 30A	no.	1
MCB 20A	no.	2
MCB 10A	no.	3
Lamp holders	no.	16
Outside lights	no.	5
Inside lights	no.	11
Double socket	no.	8
2 Lever switch/ 2 gang switch	no.	3
1 Lever switch/ 1 gang switch	no.	4
Day night switch 15A	no.	1
Cooker Unit	no.	1
BUILT IN CUPBOARDS		
Provisional amount for all Built in cupboards(Prime Cost Sum US\$15000)	sum	1

ALL PROSPECTIVE BIDDERS ARE REQUIRED TO ATTEND A COMPULSORY SITE VIST ON THURSDAY, 7 NOVEMBER, 2024 AT 11:00 AM

Bidders with outstanding orders for any of the above items will not be considered for supply

TELONE RESERVES THE RIGHT TO INCREASE AND DECREASE QUANTITY

Closing date for ALL Tenders: On or before 1100hrs; Wednesday 13 November 2024

Quotations should be in USD\$ PAYABLE IN LOCAL CURRENCY. PLEASE INSERT TENDER NUMBERS ON YOUR QUOTATION /BID

Payment Terms – 30 days

Your Tender should state the price (Please state your **VAT** status), a firm delivery date Emailed to procurement@telone.co.zw

- **Bidders should also be compliant with the new regulations for FISCAL TAX INVOICE where necessary.**
- **Each tender should be in its own envelop, tenders should not be xed on one quotation.**